No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
5	Burnt stone slab 6" thick dressed and fixed ..	S.ft.	0 5 0	595	
6	Pointing swith cement mortar	Sqr.	4 8 0	10.22	
7	Rough stone work new	C.yd.	1 12 0	45	
8	Providing joggle joints	Each	0 12 0	15	

N. SUBBA RAO,
Executive Engineer.

MYSORE DIVISION.

Notification dated 29th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M., on 20th July 1936 for Deviation of Nanjangud-Hassanurghat Road in Chamaraj Nagar Town through Parivarakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a depoist of Rs. 375 (three hundred and seventy-five) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Deviation of Nanjangud-Hassanurghat Road in Chamarajnagar Town through Parivarakere" in default of which, the tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of quantities for the deviation of Nanjangud-Hassanurghat Road in Chamarajnagar Town through Parivarakere.

No.	Items of work	Per	Quantity	Rate	Cost	Rate tendered
				Rs. a. p.	Rs.	
1	Earthwork to embankment, etc., including watering, tamping etc., complete	C.yd.	3,153	0 4 0	788	
2	Carting earth with lead of ½ a mile ..	,,	3,153	0 3 0	591	
3	Opening drains and using earth to embankment including watering and tamping	,,	496	0 4 0	124	

No.	Items of work	Per	Quantity	Rate	Cost	Rate tendered
				Rs. a. p.	Rs.	
4	Rough metal soling for the portion of the road in embankment ..	C.yd.	613	1 12 0	1,073	
5	Collection of broken metal (granite or quartz)	,,	636	2 8 6	1,617	
6	Collection of gravel	,,	260	0 4 6	73	
7	Lead for gravel 1½ miles	,,	260	0 9 0	146	
8	Consolidation of metal	,,	1,249	0 6 8	520	
9	Do of gravels	,,	260	0 4 0	65	
10	Collection and spreading sand ..	,,	20	0 8 0	10	
11	Picking road surface	,,	5,720	0 0 3	89	
12	Water rate for consolidation ..	,,	1,249	0 2 0	156	
13	Felling big trees	No.	2	25 0 0	50	
14	Removing and refixing mile and furlong stones and widening existing drains	L. S.	..	..	50	
15	Removing and resetting old revetment of Katte with new jelly	C.yd.	17	1 0 0	17	
16	Rough stone revetment new ..	,,	17	2 0 0	34	
17	Providing Teakwood caution posts including carving figures and painting and fixing in with burnt brick in chunam complete	Each	2	10 0 0	20	
	Constructing a masonry tunnel. 3′ × 3′ × 24′.					
1	Earthwork excavation for foundation	C.yd.	7	0 4 0	2	
2	Rough stone in chunam mortar for foundation	C.ft.	192	0 4 6	54	
3	Size stone in chunam mortar ..	,,	361	0 5 6	124	
4	Burnt stone slabs 8″ thick dressed and fixed in mortar	S.ft.	144	0 10 0	109	
5	Do 5″ do ..	,,	30			
6	Cement pointing to masonry ..	Sqr.	2·61	4 0 0	11	
	Constructing four tunnels. 3′ × 2′ × 24′. Quantities given below are for one tunnel.					
1	Earthwork excavation for foundation	C.yd.	7	0 4 0	2	
2	Rough stone in chunam mortar for foundation	C.ft.	192	0 4 6	54	
3	Size stone in chunam mortar ..	,,	217	0 5 6	75	
4	Burnt stone slabs 8″ thick dressed and fixed in mortar	S.ft.	144	0 10 0	109	
5	Burnt stone slabs 5″ thick dressed and fixed in mortar	,,	30	..		
6	Cement pointing to masonry ..	Sqr.	2·61	4 0 0	10	

Notification dated 29th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on 20th July 1936, for Restoring Madanaikanahalli Minor tank, Registered No. 211 of Maddur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 230 in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for Restoring Madanaikanahalli Minor tank, Register No. 211 of Maddur Taluk " in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities for restoring Madanaikanahalli Minor Tank, Register No. 211 of Maddur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost	Rates tendered
			Rs. a.p.		Rs.	
	Bund.					
1	Cutting grips to bund	Grade	0 8 0	25	13	
2	Earthwork to bund including lead and lift and watering and tamping etc., complete	C.yd.	0 4 0	8,232	2,058	
3	Turfing slopes of bund, front and rear..	S.yd.	0 0 9	6,674	313	
4	Rough stone revetment including jelly backing and lead complete ..	C.yd.	1 12 0	473	827	
5	Providing and fixing new grade stones, cutting figures and painting, etc., complete	Each	2 8 0	25	63	
6	Providing and fixing Index stones ..	,,	0 8 0	25	12	
7	Do Registered No. stone ..	,,	5 0 0	1	5	
8	Do Gauge stone ..	,,	15 0 0	1	15	
9	Do Bench mark stones ..	,,	3 0 0	2	6	
10	Removing and refixing old grade stones	,,	1 0 0	2	2	
	Repairing the old sluice.					
1	Cutting open the bund and refilling same after examination of the barrel, including watering and tamping etc., Complete	C.yd.	L. S.	..	75	
	Constructing new sluice.					
1	Earthwork excavation and using earth to bund	Cy.d.	0 4 0	141	35	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	162	41	
3	Burnt brick in surki mortar ..	,,	0 4 6	757	213	
4	Plastering with surki mortar $\frac{1}{2}$" thick .	Sqr.	3 12 0	1.36	5	
5	Burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 7 6	85	40	

No.	Items of work	Per	Rate	Quantity	Cost	Rates tendered
			Rs. a. p.	Rs.		
6	Providing and fixing 6" dia. cast iron pipes of Mysore Iron Works, Bhadravathi, including cost of pipe ..	R.ft.	2 0 0	36	72	
7	Jelly wood plug and iron rod with locking arrangements and necessary fittings, complete	Each	L. S.	..	14	
8	Removing and resetting old rough revetment including new jelly backing and wedging properly complete	C.yd.	0 12 0	9	7	
9	Earthwork refilling with lead and lift watering and tamping complete using available earth	C.yd.	0 2 0	106	13	
	Waste Weir.					
1	Earthwork excavation	C.yd.	0 4 0	99	25	
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	273	68	
3	Burnt brick in surki mortar ..	„	0 4 6	488	137	
4	Plastering with surki mortar ..	Sqr.	3 12 0	6.20	23	
5	Burnt stone slabs 6" thick dressed and fixed in surki mortar	S.ft.	0 7 6	333	166	
6	Earthwork for closing the gap of old weir including lead, watering and tamping etc., complete	C.yd.	0 4 0	80	20	
7	Rough stone work new	„	1 12 0	48	84	
8	Removing and resetting old stone revetment work with new jelly and wedging complete	„	0 12 0	31	23	

V. V. PATANKAR,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 27th June 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2 P.M. on Monday, 13th July 1936, for constructing corridors connecting the Administrative Block with Maternity and Out-patient Blocks of McGann Hospital at Shimoga. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Challan for having deposited Rs. 270 (Rupees Two Hundred and Seventy only), as earnest money, and be superscribed "Tender for constructing corridors connecting the Administrative Block with Maternity and Out-patient Blocks of McGann Hospital at Shimoga" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Enigneer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.